

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-03219-00-00
Spot: NESWNW Sec/Twnshp/Rge: 1-16S-12W
3608 feet from S Section Line, 4480 feet from E Section Line
Lease Name: SCHAUF "C" Well #: 2
County: BARTON Total Vertical Depth: 3359 feet

Operator License No.: 5259
Op Name: MAI OIL OPERATIONS, INC.
Address: 8411 PRESTON RD STE 800
DALLAS, TX 75225

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	2960		125 SX
SURF	8.625	312		175 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/26/2014 9:00 AM
Plug Co. License No.: 99977 Plug Co. Name: QUALITY OIL WELL CEMENTING
Proposal Rcvd. from: ALLEN BANGERT Company: MAI OIL CORP. Phone: (785) 483-2169

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement w/500 # hulls.
Hole full of drilling mud at 2100'.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 09/15/2014 9:00 AM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perforated at 1200' and 750'. Ran tubing to 2100' and pumped 60 sx cement w/100 # hulls.
Pulled tubing to 1200' and pumped 35 sx cement w/100 # hulls. Pulled tubing to 700'.
Circulated cement to surface w/100 sx cement and 150 # hulls. Topped off w/25 sx cement.
Tied to backside and pumped 20 sx cement. Pressured up to 200 psi.

GPS: 38.69110 -098.60578

Perfs:

Top	Bot	Thru	Comments
2870	2884		

Remarks: QUALITY OILWELL CEMENTING

Plugged through: CSG

District: 04

Signed Bruce Rodie

10/22/14 CKM

(TECHNICIAN)

Received
KANSAS CORPORATION COMMISSION

CM

OCT 06 2014

OCT 21 2014

Form CP-2/3

CONSERVATION DIVISION
WICHITA, KS