

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-193-20932-00-00
Spot: NENESWNW Sec/Twnshp/Rge: 13-9S-31W
1522 feet from N Section Line, 1107 feet from W Section Line
Lease Name: VICTOR SCHWARZ Well #: 1
County: THOMAS Total Vertical Depth: 4680 feet

Operator License No.: 30742
Op Name: PALOMINO PETROLEUM, INC.
Address: 4924 SE 84TH ST
NEWTON, KS 67114

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	255		195 sx

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 10/14/2014 12:00 AM
Plug Co. License No.: 33575 Plug Co. Name: WW DRILLING, LLC
Proposal Rcvd. from: KIRBY Company: WW DRILLING, LLC Phone: (785) 743-6774

Proposed Plugging Method: Ordered 240 sx 60/40 pozmix - 4% gel cement with 1/4# flo- seal per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: PAT STAAB WitnessType: NONE
Date/Time Plugging Completed: 10/14/2014 11:30 AM KCC Agent: PAT STAAB

Actual Plugging Report:

1st plug @2589 w/50 sx
2nd plug @1717 w/100 sx
3rd plug @305 w/50 sx
4th plug @40 w/10 sx

Rathole 30 sx


Perfs:

Remarks: ALLIED

Plugged through: DP

District: 04

Signed _____


10/22/14 CKM (TECHNICIAN)

Received
KANSAS CORPORATION COMMISSION Form CP-2/3

OCT 21 2014

CONSERVATION DIVISION
WICHITA, KS