

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-24287-00-00
Spot: SWSWSWNE Sec/Twnshp/Rge: 15-17S-21W
2606 feet from N Section Line, 2466 feet from E Section Line
Lease Name: CONNER-WIERMAN Well #: 1-15
County: NESS Total Vertical Depth: 4231 feet

Operator License No.: 30717
Op Name: DOWNING-NELSON OIL CO INC
Address: PO BOX 1019
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4127		
DVT		1465		WITH 180 SX CMT
PROD	5.5	4227	0	WITH 150 SX CMT
SURF	8.625	223		WITH 150 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/08/2014 10:00 AM
Plug Co. License No.: 99977 Plug Co. Name: QUALITY OIL WELL CEMENTING
Proposal Rcvd. from: BRIAN KARLIN Company: DOWNING NELSON Phone: (785) 623-3290

Proposed Plugging Method: RUN TBG TO 4100' & SPOT 30 SX CMT WITH 150# HULLS. PLUG AT 1500' WITH 25 SX CMT. CIRCULATE CMT TO SURFACE FROM 800'. CHECK BACKSIDE WITH CMT.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/08/2014 1:45 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

RUN TBG TO 4100' & PUMP 30 SX CMT & 150# HULLS. PULL TBG TO 1500' & PUMP 50 SX CMT. PULL TBG TO 800' & PUMP 160 SX CMT. CMT CIRCULATED TO SURFACE. PULLED TBG & TOPPED OFF WITH 15 SX CMT. TIED ONTO BACKSIDE. PRESSURED TO 500# & HELD.

Perfs:

Top	Bot	Thru	Comments
4180	4186		

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY OIL WELL CEMENTING.

Plugged through: TBG

District: 01

Signed Michael Maier
KANSAS CORPORATION COMMISSION (TECHNICIAN)

RECEIVED
OCT - 9 2014
KCC DODGE CITY

OCT 15 2014
CONSERVATION DIVISION
WICHITA, KS

10/15/14 CKM

Form CP-2/3