

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-151-22417-00-00
Spot: SWSEW Sec/Twnshp/Rge: 24-29S-13W
2307 feet from N Section Line, 1630 feet from W Section Line
Lease Name: BARNHART Well #: 24-1
County: PRATT Total Vertical Depth: 4800 feet

Operator License No.: 34506
Op Name: EMPIRE ENERGY E&P, LLC
Address: 345 RIVERVIEW ST., STE 540
WICHITA, KS 67203

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|-----------------|
| CIBP | | 4450 | | WITH 2 SX CMT |
| PROD | 5.5 | 4803 | 2195 | WITH 265 SX CMT |
| SURF | 8.625 | 813 | | WITH 200 SX CMT |

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/06/2014 1:00 PM
Plug Co. License No.: 30891 Plug Co. Name: LEIKER WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD LACEY Company: EMPIRE ENERGY E & P Phone: (620) 617-0603

Proposed Plugging Method: Bottom Plug: Set CIBP @ 4450' w/ 2sx cement Top Plug: Spot plugs through casing while pulling. 1st plug @ 850' w/ 10 sx gel - 50sx cement, 400' w/ 40 sx cement, 40' w/ 10 sx cement. 60/40 Pozmix 4% Gel

Plugging Proposal Received By: KENNY SULLIVAN Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/06/2014 3:30 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP @ 4450' & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. 1ST PLUG AT 853' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 390' WITH 40 SX CMT. 3RD PLUG AT 42' WITH 10 SX CMT.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 4500 | 4510 | | |

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: CSG

District: 01

RECEIVED
OCT - 8 2014
KCC DODGE CITY

Signed Stephens J. Pfeifer
(TECHNICIAN)
Received
KANSAS CORPORATION COMMISSION
10/15/14 CKM

OCT 15 2014
CONSERVATION DIVISION
WICHITA, KS