

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-20407-00-00
Spot: NWNENWSE Sec/Twnshp/Rge: 16-33S-11W
2308 feet from S Section Line, 1660 feet from E Section Line
Lease Name: PAGE C Well #: 11
County: BARBER Total Vertical Depth: 4572 feet

Operator License No.: 3273
Op Name: HERMAN L. LOEB, LLC
Address: PO BOX 838
LAWRENCEVILLE, IL 62439

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4450		
PROD	5.5	4569	0	WITH 200 SX CMT
SURF	8.625	202		WITH 150 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/02/2014 8:00 AM
Plug Co. License No.: 34109 Plug Co. Name: M & M WELL SERVICE, LLC
Proposal Rcvd. from: ALAN VRATIL Company: HERMAN L. LOEB LLC Phone: (618) 943-2227

Proposed Plugging Method: SET CIBP @ 4450' & 2 SX CMT. PLUG AT 1200' WITH 25 SX CMT. PERFORATE AT 600' & CIRCULATE CMT TO SURFACE IN & PUT OF 5 1/2" CASING.

Plugging Proposal Received By: ERIC MACLAREN Witness Type: NONE
Date/Time Plugging Completed: 10/03/2014 12:00 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP @ 4450' & 2 SX CMT. 1ST PLUG SPOT 40 SX COMMON CMT W/3% CC. LET CMT SET. TAG TOC @ 1102'. 2ND PLUG PERFORATE AT 600'. UNABLE TO PUMP INTO. PRESSURE TO 500#. ALSO PRESSURE UP 5 1/2" X 8 5/8" ANNULUS TO 500#. RAN BOND LOG. FOUND CMT BOND FROM 800' TO 164'. LOST SINGLE. SUSPECT CMT TO SURFACE. PERFORATE AT 154'. UNABLE TO PUMP INTO PERFS AT 154'. PRESSURE UP ON CASING & ANNULUS TO 500#. RUN TBG TO 600'. FILL INSIDE OF 5 1/2" CASING TO SURFACE WITH 55 SX CMT.

Perfs:


Top	Bot	Thru	Comments
4492	4520		

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

Signed


(TECHNICIAN)

RECEIVED

OCT - 9 2014

KCC DODGE CITY

Received
KANSAS CORPORATION COMMISSION

OCT 15 2014

CONSERVATION DIVISION
WICHITA, KS

10/15/14 

Form CP-2/3