

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-125-32248-00-00
Spot: NWNWSENW Sec/Twnshp/Rge: 24-33S-14E
3782 feet from S Section Line, 3758 feet from E Section Line
Lease Name: WILEY Well #: 1
County: MONTGOMERY Total Vertical Depth: 1264 feet

Operator License No.: 31486
Op Name: HORTON, JACK
Address: 1958 COUNTY RD 3000
INDEPENDENCE, KS 67301

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	1216		135 SX
SURF	8.625	22		12 SX
T1	2.375	1140		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/05/2014 12:00 AM
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.
Proposal Rcvd. from: AUSTIN DAVIS Company: _____ Phone: (620) 673-4812

Proposed Plugging Method: Run 1" to TD. Spot 10sx portland cement on bottom Gel hole & pull up to 850', spot 5 sx @ 850' Gel hole & pull up to 250', spot 25 sx @ 250' to surface

Plugging Proposal Received By: DUANE SIMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/05/2014 10:00 AM KCC Agent: DUANE SIMS

Actual Plugging Report:

Ran 1" to 1200' gelled hole and spotted 10 sack plug. Pulled up to 850' and spotted 5 sack plug. Pulled up to 250' and circulated cement to surface. Pulled 1" and topped well off. A total of 44 sacks of cement were used to plug this well.

Perfs:

Top	Bot	Thru	Comments
1123	1130		

RECEIVED
OCT 07 2014
KCC Chanute Dist. #3
DS

Remarks:

Plugged through: TBG

District: 03

Signed

Duane A Sims
(TECHNICIAN)

10/15/14 CCM

Received
KANSAS CORPORATION COMMISSION

OCT 09 2014

CONSERVATION DIVISION
WICHITA, KS