

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-151-22205-00-00  
Spot: NW Sec/Twnshp/Rge: 25-26S-11W  
1279 feet from N Section Line, 1341 feet from W Section Line  
Lease Name: ZINK Well #: 1  
County: PRATT Total Vertical Depth: 4375 feet

Operator License No.: 6039  
Op Name: L. D. DRILLING, INC.  
Address: 7 SW 26TH AVE  
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4250		WITH 2 SX CMT
PROD	5.5	4373	2226	WITH 199 SX CMT
SURF	8.625	454		WITH 350 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/06/2014 11:00 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: JAMIE HARRIS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2943

Proposed Plugging Method: CIBP @ 4250' WITH 2 SX CMT. PLUG AT 600' WITH 10 SX GEL & 80 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 10/06/2014 12:30 PM KCC Agent: ROBERT DICKERSON

Actual Plugging Report:

SET CIBP @ 4250' WITH 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. 1ST PLUG AT 600' WITH 10 SX GEL & 80 SX CMT. CIRCULATED. 2ND PLUG AT 40' WITH 20 SX CMT. CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
4289	4292		

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND.

Plugged through: CSG

District: 01

Signed Robert Dickerson  
(TECHNICIAN)

RECEIVED  
OCT - 8 2014  
KCC DODGE CITY

Received  
KANSAS CORPORATION COMMISSION  
OCT 15 2014  
CONSERVATION DIVISION  
WICHITA, KS

10/15/14 CKM  
SI