

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-151-22235-00-00
Spot: E2E2SWSW Sec/Twnshp/Rge: 24-26S-11W
660 feet from S Section Line, 1050 feet from W Section Line
Lease Name: ZINK "B" Well #: 1
County: PRATT Total Vertical Depth: 4367 feet

Operator License No.: 6039
Op Name: L. D. DRILLING, INC.
Address: 7 SW 26TH AVE
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4250		WITH 2 SX CMT
PROD	5.5	4361	2210	WITH 200 SX CMT
SURF	8.625	479		WITH 350 SX CMT

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 10/08/2014 3:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: JAMIE HARRIS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2943

Proposed Plugging Method: CIBP @ 4250' WITH 2 SX CMT. PLUG AT 710' WITH 10 SX GEL & 40 SX CMT. PLUG AT 500' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/08/2014 4:45 PM KCC Agent: ROBERT DICKERSON

Actual Plugging Report:

SET CIBP @ 4250' WITH 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. 1ST PLUG AT 710' WITH 10 SX GEL & 40 SX CMT. 2ND PLUG AT 500' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4290	4293		

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND ACID & CMT.

Plugged through: CSG

District: 01

Signed Robert Dickerson

(TECHNICIAN)

RECEIVED
OCT 13 2014
KCC DODGE CITY

Received
KANSAS CORPORATION COMMISSION

OCT 15 2014

CONSERVATION DIVISION
WICHITA, KS

10/15/14 CKM

Form CP-2/3