

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-063-21952-00-00  
Spot: NESWSWSW Sec/Twnshp/Rge: 33-12S-31W  
485 feet from S Section Line, 350 feet from W Section Line  
Lease Name: ANDERSEN FARMS UNIT Well #: 1-33  
County: GOVE Total Vertical Depth: 4700 feet

Operator License No.: 5214  
Op Name: LARIO OIL & GAS COMPANY  
Address: 301 S MARKET ST  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4695		140 SX
SURF	8.625	265		150 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/08/2014 12:20 PM  
Plug Co. License No.: 33645 Plug Co. Name: H2 PLAINS, LLC  
Proposal Rcvd. from: LARRY KARLIN Company: LARIO O & G COMPANY Phone: (620) 277-2149

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/250 # hulls.  
8 5/8" surface casing set at 265' w/150 sx cement. 4 1/2" production casing set at 4695' w/140 sx cement. DV tool set at 2260' w/480 sx cement. Perforations: 4534' - 4538' and 4546' - 4550'. TD 4700'.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 10/08/2014 12:20 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Ran tubing to 4488' and pumped 100 sx cement w/250 # hulls. Pulled tubing to 2995' and pumped 100 sx cement. Pulled tubing to 1502' and pumped 100 sx cement. Cement to surface. Pulled tubing to surface. Connected to 4 1/2" casing and pumped 15 sx cement. Cement visible in 8 5/8" casing.

GPS: 38.96203N -100.77691W

Perfs:

Top	Bot	Thru	Comments
4546	4550		
4534	4538		

Remarks: CONSOLIDATED OIL WELL SERVICES TICKET # 46,692

Plugged through: TBG

Received  
KANSAS CORPORATION COMMISSION  
OCT 15 2014  
CONSERVATION DIVISION  
WICHITA, KS

District: 04

Signed Darrel Dipman  
10/15/14 ccm (TECHNICIAN)

cm

OCT 09 2014