

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-023-20574-00-00
Spot: W2NENWNE Sec/Twnshp/Rge: 31-4S-41W
330 feet from N Section Line, 1800 feet from E Section Line
Lease Name: HARKINS Well #: 4-31
County: CHEYENNE Total Vertical Depth: 1365 feet

Operator License No.: 30282
Op Name: LOBO PRODUCTION, INC
Address: 2035 RD 68
GOODLAND, KS 67735

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	1357		55 SX
SURF	7	170		35 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 10/01/2014 9:00 AM
Plug Co. License No.: 30282 Plug Co. Name: LOBO PRODUCTION, INC
Proposal Rcvd. from: RICHARD MILLER Company: LOBO PRODUCTION, INC Phone: (785) 899-7277

Proposed Plugging Method: 7" Surface pipe set at 170' w/35 sx cement. 4 1/2" production casing set at 1357' w/55 sx cement. TD 1365'. PBTB 1332'.
The casing was not perforated.
Ordered 85 sx common cement

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/01/2014 11:30 AM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Perfs:

Swabbed production casing to TD. Ran tubing to 500' and pumped 60 sx cement. Cement to surface. Pulled tubing to surface and pumped 22 sx cement. Production casing full. Visible cement in 7" surface casing. Plug complete.

GPS: 39.66864 -101.96227

Remarks: SCHOSSER REDI MIX TICKET # 1063. COMPANY TOOLS.

Plugged through: TBG

Received
KANSAS CORPORATION COMMISSION
OCT 15 2014
CONSERVATION DIVISION
WICHITA, KS

District: 04

Signed

Darrel Dipman

(TECHNICIAN)

10/15/14 CM

CM

Form CP-2/3

OCT 06 2014