

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas. 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

15-051-20265-0000

API NUMBER 6-11-68

LEASE NAME A. North

WELL NUMBER #8

App. on. 660 Ft. from S Section Line

App. on. 2150 Ft. from E Section Line

SEC. 28 TWP. 15S RGE. 20 (E or W)

COUNTY Ellis

Date Well Completed 6-11-68

Plugging Commenced 2-14-86

Plugging Completed 2-14-86

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Rains & Williamson Oil Co. Inc.

ADDRESS 435 Page Court - 220 West Douglas Wichita, Kan.

PHONE # (316) 265-9686 OPERATORS LICENSE NO. 5146

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays

Is ACO-1 filed? Yes If not, is well log attached? Yes

Producing Formation Conglomerate Sand Depth to Top 3965 Bottom 3976 T.D. 3976

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
<u>Conglomerate Sand</u>	<u>3965 - 3976</u>			<u>5 1/2</u>	<u>3974 1/2</u>	<u>None</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set.

8-1/2" Titan, Down 8 1/2" with 50 sk. cement 60/40 por mix 6% gel 3% C.C. with 1sk hulls. Max. press. 600 lbs. Shut in at 300 lbs. Down 5 1/2" with 2sk. hulls, followed with 50 sk. cement 60/40 por mix 6% gel 3% C.C. with 1sk hulls, 100 sk. cement, released plug, followed with 10 sk. cement, Max. press. 2000 lbs. Shut in at 1800 lbs. Thugged down at 12:20 PM. Starts agent
 (If additional description is necessary, use BACK of this form.) Marion Schmidt

Name of Plugging Contractor Paul Stephens License No. 683

Address P.O. Box 166

STATE OF Kansas COUNTY OF Pratt, ss.

Rains & Williamson Oil Co. Inc. (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts stated, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) Paul Stephens

(Address) _____

SUBSCRIBED AND SWORN TO before me this 18th day of Feb., 19 86

Mary Alice Rupp
 Notary Public

My Commission Expires: 2-29-88



Handwritten: RWD 02-21-86