


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

15-009-06916-0000  
WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Location as "NE/CNW/SW" or footage from lines Barton County. Sec. 18 Twp. 20S Rge. (E) 12 (W) (W)  
Lease Owner The Bay Petroleum Corporation  
Lease Name Huscinka Well No. 4  
Office Address Box 957 Denver Colorado  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed May 2 19 49  
Application for plugging filed November 20 19 52  
Application for plugging approved (oral) November 5 19 52  
Plugging commenced November 5 19 52  
Plugging completed November 7 19 52  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production None 19       
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well C.D. Stough  
Producing formation      Depth to top      Bottom      Total Depth of Well 3551 Feet  
Show depth and thickness of all water, oil and gas formations. 3225' PB

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	363'	None
				5 1/2"	3481'	2611'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from      feet to      feet for each plug set.

Sanded hole from 3225' to 3200' and ran 5 sacks of cement.  
Mudded hole from 3200' to 250', set 10' rock bridge from  
250' to 240' and ran 20 sacks of cement. Mudded hole to  
40', set 10' rock bridge and ran 10 sacks of cement.

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 22 1952  
11-22-52  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor West Supply Company  
Address Chase Kansas

STATE OF Kansas, COUNTY OF Rice, ss.  
Glen E. Armour (employee of owner) or (owner) or (operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Glen E. Armour

(Address)

SUBSCRIBED AND SWORN TO before me this 20 day of November, 19 52

My commission expires May 20 1954

24-2675-S 2-52-20M



PLUGGING  
FILE SEC 18 20 R 123  
BOOK PAGE 58 LINE 3

Notary Public.

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY  
412 Union National Bk. Bldg., Wichita, Kansas

Company - C. U. BAY  
Farm - Huschka


No. 4

SEC. 18 T. 20 R. 12W  
NE SE NW

Total Depth. 3551  
Comm. 3-13-49 Comp. 5-2-49  
Shot or Treated. acidized  
Contractor. Lewis Drilling  
Issued. 7-2-49

County. Barton

KANSAS



Elevation. \_\_\_\_\_

Production. Dry

CASING:  
8 5/8" 363'  
5 1/2" 3481'

Figures Indicate Bottom of Formations.

surface sand, clay	112
iron, sand	132
shale, shells	360
red bed	460
red rock, shale	655
limo	680
shale, shells	1665
lime, shale	1860
lime	1950
lime, shale	2535
lime	3055
lime, shale	3190
limo RTD	3493
dolomite	3551
Total Depth	

TOPS:

Brown Lime Lansing	3184	3169
Conglomerate		3424
Arbuckle		3478

Perf. 12 shots @3208-10 no show  
1000 acid, 1 1/2 BW PH rainbow oil  
48 shots 3252-62 no show  
1000 acid  
1 gal oil per hr, 1 1/2 gal wtr per hr  
Perf. 72 shots 3316-28, 1000 acid  
swab 700' wtr in 30 min. no oil  
Perf. 6 shots per foot 3182-96,  
1000 acid no help 24 shots 3252-58  
2000 acid DD 3551 HFW syz/ perf.  
perf. 24 shots 3210-14  
perf. 24 shots 3232-38  
24 shots 3244-48  
8000 acid tested 50' WPH scum oil

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 22 1952  
CONSULTATION DIVISION  
Wichita, Kansas

PLUGGING  
FILE SEC 18 T 20 R 12W  
BOOK PAGE 58 LINE 3