

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Barton County. Sec. 18 Twp. 20S Rge. 12W (E) (W)

Location as "NE/CNW/SW" or footage from lines. SW NE NW

Lease Owner Bay Petroleum Corporation

Lease Name Huschka Well No. 3

Office Address Chase, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Oil Well

Date well completed March 19 19 49

Application for plugging filed January 7 19 54

Application for plugging approved January 8 19 54

Plugging commenced January 9 19 54

Plugging completed January 13 19 54

Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production September 26 19 53

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Warren Horner

Producing formation Kansas City Depth to top 3174 Bottom _____ Total Depth of Well _____ Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	355'	None
				5-1/2"	3440'	2506'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with sand from 3185' to 3170' and ran 5 sacks of cement which filled to 3135'. Set a rock bridge from 300' to 290' and ran 20 sacks of cement which filled to 230'. Mudded hole to 40', set a 10' rock bridge and ran 10 sacks of cement to fill to top. Plugging completed.

STATE CORPORATION COMMISSION

JAN 20 1954 01-20-54

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor West Supply Company
Address Chase, Kansas

STATE OF Kansas, COUNTY OF Rice, ss. Glen E. Armour (employee of owner) or (owner) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) Glen E. Armour

(Address)

SUBSCRIBED AND SWORN TO before me this 19 day of January, 19 54

My commission expires May 20 1954

Wesley O. Gray
Notary Public.



WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bldg., Wichita, Kansas


Company - C. U. BAY
Farm - Huschka

No. 3

SEC. 18 T. 20 R. 12W
SW NE NW

Total Depth. 3442
Comm. 3-1-49 Comp. 3-11-49
Shot or Treated. Acid
Contractor. Lewis Drilling Co.
Issued. 5-14-49

County. Barton
KANSAS



CASING:
8 5/8" 355'
5 1/2" 3440'

Elevation. _____

Production. 294 BOPD

Figures indicate Bottom of Formations.

collar	5
sand	60
sand, shells	105
sand, iron	144
shale	355
red bed, shale	700
shale	825
shale, shells	1420
lime, shale	2210
shale, shells	2715
lime, shale	2915
lime	3006
lime, shale	3159
lime	3407
lime, conglomerate	3437
lime	3442
Total depth	

Tops:
Brown lime 3160
Lansing 3174
Conglomerate 3412
Arbuckle 3439

Testing Information:

Perf. 24 shots 3191-95.
Perf. 24 shots 3198-3203.
1000 acid, swb 5 BOPH, FU 1200'
no time.
2000 acid, does not flow.
Total fillup 2700'.

RECEIVED
STATE OF KANSAS
JAN 20 1951
CONSERVATION DIVISION
Wichita, Kansas

Chase

PLUGGING
FILE SEC 18 T 20 R 12W
BOOK PAGE 6 LINE 28