


Give Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Wooley Barton County. Sec. 18 Twp. 20 Rge. (E) 12 (W)
Location as "NE/CNW/SW" or footage from lines NE NE Se
Lease Owner Cooperative Refinery Association
Lease Name Wooley "A" Well No. 1
Office Address Box 765 Gt. Bend, Ks.
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole
Date well completed March 19 19 59
Application for plugging filed March 23 19 59
Application for plugging approved Verbal permission obtained 19 59
Plugging commenced March 19 19 59
Plugging completed March 19 19 59
Reason for abandonment of well or producing formation dry hole

If a producing well is abandoned, date of last production _____ 19 ____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes, verbal permission

Name of Conservation Agent who supervised plugging of this well Don Truan
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3515 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	662	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole to 350' with mud, set plug, dumped 1 sx. hulls, used 25sx. cement, filled to 40' with mud, used 1/3 sx. hulls and plug, cemented with 10 sx. Filled to bottom of cellar.

RECEIVED
STATE CORPORATION COMMISSION

MAR 25 1959

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Shields Drlg. Company
Address Russell, Ks.

STATE OF KANSAS, COUNTY OF BARTON, ss.
Marvin D. Sullivan (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Marvin D. Sullivan
Box 765 Gt. Bend, Ks.
(Address)

SUBSCRIBED AND SWORN TO before me this 23 day of March, 19 59

My commission expires Sept. 24, 1960

Gyonne Adams
Notary Public.

PLUGGING
FILE SEC. 18 T. 20 R. 12W
BOOK PAGE 25 LINE 8

DRILLERS LOG:

Wooley "A" #1

Elevation: 1843
 Casing: 8 5/8" @ 662'
 @/ 425 sx.

Loc: NE NE SE
 Sec: 18-20-12W
 Barton County, Kansas
 Operator: Cooperative Refinery Ass'n.
 Contractor: Shields Drlg. Company

Comm: 3-8-59 Comp: 3-19-59
 R.T.D. 3515

<u>From</u>	<u>To</u>	<u>Formation</u>
0	75	Sand
75	105	Sand, pyrite, shale
105	652	Shale, shells, redbed
652	680	Anhydrite
680	1520	Shale and shells
1520	1655	Shale and broken lime
1655	1820	Broken lime
1820	2780	Lime and shale
2780	3025	Lime
3025	3190	Lime and shale
3190	3515	Lime
3515		R.T.D.

RECEIVED
 STATE CORPORATION COMMISSION
 MAR 25 1959
 CONSERVATION DIVISION
 Wichita, Kansas

(STATE OF KANSAS)

(COUNTY OF BARTON)

I hereby certify that the above is a true and correct copy of the log on the Wooley "A" #1 well located NE NE SE of Section 18-20-12W, Barton County, Kansas.

Martin Sullivan

Subscribed and sworn to before me this 23 day of March 1959.

Yvonne Adams

My commission expires: Sept. 24, 1960.

PLUGGING
 FILE SEC. 18 T. 20 R. 12W
 BOOK PAGE 25 LINE 8