

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-009-22,744 0000

LEASE NAME Sessler

WELL NUMBER #2

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

330 Ft. from N Section Line

1060 Ft. from E Section Line

SEC. 18 TWP. 20 RGE. 12W (E) or (W)

COUNTY Barton

LEASE OPERATOR Carl Boxberger Oil, Inc.

ADDRESS P.O. Box 1604 Great Bend, Ks. 67530

PHONE# (316) 793-6032 OPERATORS LICENSE NO. 4707

Date Well Completed _____

Character of Well Oil

Plugging Commenced 5-12-93

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 5-18-93

The plugging proposal was approved on _____ (date)

by Hubert Deines (KCC District Agent's Name).

Is ACO-1 filled? _____ If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom T.D. 3625'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	320'	none
				5-1/2"	3624'	2225'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set. Plugged off bottom with sand to 3170' and 5 sacks cement. Shot pipe @2611', 2425', 2225', pulled up to 1580' and pumped 35 sacks cement, pumped 25 sacks @780', circulated cement from 370' to surface, 60/40 pos, 6%. Plugging Complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor KELSO CASING PULLING, INC. License No. _____

Address P.O. Box 347 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Carl Boxberger Oil, Inc.

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) P.O. Box 347 Chase, KS. 67524

SUBSCRIBED AND SWORN TO before me this 19th day of May, 19 93

Jane S. Sessler
Notary Public

My Commission Expires: _____



RECEIVED
STATE CORPORATION COMMISSION
MAY 20 1993
CONSERVATION DIVISION
Wichita, Kansas