


WELL PLUGGING RECORD

15-009-15551-0000

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Location Barton County Sec 18 Twp 20 Rge 12 (E) (W)
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SW NW NW
Lease Owner Ray Petro Co
Lease Name Huschka Well No. 6
Office Address Chase, Kansas
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 4/16/50 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 4/14/50 19
Plugging completed 4/16/50 19
Reason for abandonment of well or producing formation
If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Name of Conservation Agent who supervised plugging of this well Stough
Producing formation Depth to top Bottom Total Depth of Well Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				5 1/2	3441	2511 5"
				8 5/8	250	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Locked hole from 3150 to 3135. Run 5 sks cement.
Set rock bridge to 195. Run 15 sks cement.
Mudded to 30. Run 10 sks cement. Well Complete.


JUL 8 - 1950 07-03-50
CONSERVATION DIVISION
KANSAS

(If additional description is necessary, use BACK of this sheet)
Correspondence regarding this well should be addressed to Ray Petroleum Co
Address Chase, Kansas

STATE OF Kansas COUNTY OF Rice, ss.
James Crawford (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.
(Signature) James Crawford

SUBSCRIBED AND SWORN TO before me this 1 day of July, 1950
Vincent O. Gray Notary Public

My commission expires May 20, 1954



WELL LOG BUREAU — KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company- C.U. BAY
Farm. Huschka

No. 6.

SEC. 18 T. 20 R. 12W
SW NW NW

Total Depth 3465'

Comm. 4-5-49 Comp. 6-7-49

County. Barton
KANSAS

Shot or treated. acidized
Contractor, Pickrell Drilling
Issued. 7-2-49

CASING

8 5/8" 363' cem. w/200 sx.
5 1/2" 3441' cem. w/150 sx

Elevation _____

Production. 32 B0, no wtr

Figures Indicate Bottom of Formations

sand, shale 117
iron pyrite 125
shale 250
shale.lime, shells 290
red rock 363
shale 405
red rock 655
lime 670
red rock, lime, shells 1125
red rock, salt 1470
lime, shells, shale 1685
lime brkn 1810
lime 1875
lime, shale 2806
lime 3085
lime, shale 3150
lime 3448
lime ? 3465
Total Depth

Circ. for samples 3226
" " " 3230
Drill Stem Tested 3230
Circ. for samples 3319
" " " 3341
" " " 3436
" " " 3448

TOPS:

Brown Lansing 3167
Lansing 3183
Conglomerate 3418
Arbuckle 3440

DD 19' to 3465'
HFW rainbow oil
Lane Wells plug perf. 24 shots 3180-96
Perf. 24 shots 3200-08
Perf. 24 shots 3214-22
1000 acid 14 GWPB & scum oil
Perf. 96 shots 3226-42
1000 acid 5 GO & 10 GWPB
3000 acid 15 GO & 20 GWPB
Filled up 400' overnight w/oil and water

RECORDED
INDEXED
APR 28 1950
STATE OF KANSAS
COMMISSIONER
KANSAS

PLUGGING
FILE SEC. 18 T. 20 R. 12W
BOOK PAGE 3 LINE 10