


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Biting Building  
Wichita, Kansas

Barton County, Sec. 5 Twp. 20 Rge. 12 (W)

NORTH



Locate well correctly on above Section Plat

Location as "NE/CNW%SW%" or footage from lines SW SE NW  
Lease Owner Hilton Drilling Company, Inc.  
Lease Name Steckel Estate Well No. 1  
Office Address 2421 Tenth Street, Great Bend, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed October 12, 1954 19  
Application for plugging filed October 12, 1954 19  
Application for plugging approved October 12, 1954 19  
Plugging commenced October 12, 1954 19  
Plugging completed October 12, 1954 19  
Reason for abandonment of well or producing formation dry hole

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? \_\_\_\_\_

Name of Conservation Agent who supervised plugging of this well Warren Horner  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3467 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	134	8-5/8"	134	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

80 sacks cement pumped down by Globe Cementing Company  
Plugged ahead of cement  
Pumped down with 375# Max. Pressure  
Shut in pressure 125#

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Globe Oilwell Cementing Company  
Address Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.  
Dan Cook, Vice-President (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dan A. Cook Vice-President  
Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 14th day of October, 1954

Carmen Reinhardt Leiber  
Notary Public.

My commission expires January 26, 1955

PLUGGING  
TRK SEC. 5 TWP. 20 R. 12W  
BOOK PAGE 20 LINE 35

10-15-54

D R I L L E R ' S   L O G

COMPANY: HILTON DRILLING COMPANY, INC.                      LOCATION: SW of SE of NW  
CONTRACTOR: HILTON DRILLING COMPANY, INC.                      Sec. 5-20S-12W  
FARM NAME: STECKEL ESTATE NO. 1                                      Barton County, Kansas  
COMMENCED: 9-30-54                                                      ELEVATION: 1827 K.B.  
COMPLETED: 10-12-54                                                      Casing Used: 8-5/8" @ 134' w/175 sx.

---

Surface Sand & Clay	121
Hard Sand & Pyrite	126
Sand	132
Hard Sand & Pyrite	134
Very Hard Sand	150
Blue Shale & Clay	300
Red Bed & Shale	645
Anhydrite	672
Red Bed & Shale	765
Shale & Shells	1090
Shale & salt	1350
Shale & shells	1530
Bro.Lime & Shale	1575
Lime & Hard Sand	1605
Brown Lime	1805
Lime & Shale	1920
Brown Lime & Shale	2225
Shale & Lime Streaks	2395
Shale & Lime	2550
Shale & Lime & Shells	2605
Lime	2635
Shale & Shells	2660
Lime	2820
Lime & Shale	2893
Lime	2985
Lime & Shale	3137
Lime	3385
Conglomerate	3409
Lime	3467
Total Depth	3467

---

STATE OF KANSAS            )  
                                          ) ss.  
COUNTY OF BARTON        )


I, the undersigned, being duly sworn on oath, state that the above statement and log are true and a correct record and log of the well drilled at the location above described.

HILTON DRILLING COMPANY, INC.

  
Henry Peacock, Secretary

Subscribed and sworn to before me this 12th day of October, 1954:

My commission expires: 1-26-55

  
Carmen Reinhardt Leiber  
Notary Public

