

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Barton County, Sec. 14 Twp. 20 Rge. 13 (E) W (W)

Location as "NE/CNW&SW&" or footage from lines SE SE SE

Lease Owner Harms-Burt Drilling Company

Lease Name Weathers Well No. 1

Office Address Box 184, Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed March 4 19 55

Application for plugging filed March 4 19 55

Application for plugging approved March 4 (orally) 19 55

Plugging commenced March 4 19 55

Plugging completed March 4 19 55

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19 _____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Warren H. Horner, Box 207, Great Bend, Kans.

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3510 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface		0	200	8 5/8"	200'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with mud from 3510 to 200'
Set plug at 200' with 20 sacks cement on top.
Heavy mud to 35'. Set plug at 35' with 10 sacks cement on top of plug.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Harms-Burt Drilling Company

Address Box 184, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.

Allan Harms (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Allan Harms

Box 184, Great Bend, Kans.
(Address)

SUBSCRIBED AND SWORN TO before me this 14 day of April, 19 55

Mary E Van Pelt
Notary Public.

My commission expires 1-20-58

PLUGGING
FILE SEC 14 T 20 R 13
BOOK PAGE 122 LINE 27
APR 15 1955
WICHITA, KANSAS

Driller's Log

Company: Harms-Burt Drilling Co.

Farm: Weathers No. 1

SE SE SE

Sec. 14-20S-13W, Barton County, Kans.

Commenced: February 21, 1955

Completed: March 4, 1955

Elevation: 1862 KB

0 - 40	Surface clay and sand	2100 - 2910	Shale & lime
40 - 120	Sand	2910 - 2970	lime
120 - 200	Shale & shells	2970 - 3116	Lime & shale
200 - 673	Shale, red bed	3116 - 3119	Heebner shale
673 - 705	Anhydrite	3119 - 3134	Lime & shale
705 - 950	Red bed & shale	3134 - 3200	Shale
950 - 1275	Shale & shells with salt	3200 - 3213	Brown lime
1275 - 1500	Shale & shells	3213 - 3437	Lansing - Kansas City lime
1500 - 1600	Shale & lime	3437 - 3452	Lime & shale
1600 - 1825	Lime	3452 - 3503	Conglomerate
1825 - 1905	Lime and shale	3503 - 3510	Arbuckle dolomite
1905 - 2100	Shale & shells	3510	T.D.

Set 200 feet of 8 5/8" surface pipe. Cemented with 200 sacks common cement and 5 sacks of calcium chloride.

Tops:	Anhydrite	643
	Heebner	3082
	Brown Lime	3200
	Lansing KC	3213
	Conglomerate	3452
	Arbuckle	3499

Drill Stem Tests: No. 1 3216 - 3251 feet, Open 1/2 hr. 6' mud
BHP 8# in 15 min.
No. 2 3337 - 3354 feet. Open 1/2 hr. 8' mud.
BHP 220# in 15 min.

Dry, plugged and abandoned.

Affidavit: State of Kansas)
County of Barton) SS.

I, Allan Harms of Harms-Burt Drilling Company, being first duly sworn on oath state that I have knowledge of the facts, statements, and matters herein contained and that the same are true and correct.

Signed *Allan Harms*

Subscribed and sworn to before me this 14 day of April, 1955.

Comm. Exp. 1-20-58

Mary E Van Pelt
Notary Public

STATE OF KANSAS
APR 15 1955
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING

FILE SEC 14 T 20 R 13W
PAGE 102 LINE 27