

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-151-20112-00-01  
Spot: SENWSW Sec/Twnshp/Rge: 5-27S-12W  
1650 feet from S Section Line, 4335 feet from E Section Line  
Lease/Unit Name: DIKEMAN Well Number: 1  
County: PRATT Total Vertical Depth: 4512 feet

Operator License No.: 31056  
Op Name: BULLSEYE OILFIELD SERVICE  
Address: 324 SIMPSON PO BOX 8778  
PRATT, KS 67124

Production Casing Size: 5.5 feet: 4512 WITH 200 SX CMT  
Surface Casing Size: 8.625 feet: 671 WITH 500 SX CMT

8146.64

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/03/2003 1:00 PM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: TRACY CHAMBERS Company: BULLSEYE OILFIELD SERVICE Phone: (620) 672-7240

Proposed Plugging Method: SAND TO 4250' & 4 SX CMT. PLUG AT 1000' WITH 40 SX CMT. PLUG AT 700' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE MIDDLETON WitnessType: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 06/03/2003 2:00 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:  
PERFS AT 4292-94 & 4404-07'. SANDED BACK TO 4250' & PUT 5 SX CMT ON TOP OF SAND BRIDGE THROUGH DUMP BAILER. SPOT PLUGS THROUGH 5 1/2" CASING. 1ST PLUG AT 700' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 300' WITH 40 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

RECEIVED  
JUN 19 2003  
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2400' OF 5 1/2" CASING.

Plugged through: CSG

District: 01

RECEIVED  
JUN 10 2003  
KCC Dodge City

Signed Stephen J. Pfeifer  
(TECHNICIAN)

INVOICED  
DATE 6-19-03  
200 3061653

Form CP 2/3