

To: 1040949  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-151-22,135-00-00  
150' S of  
W/2 NW NW, SEC. 16, T 27 S, R 12 W/E  
810 feet from NXS section line  
330 feet from WXX section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 5316  
Operator: Falcon Exploration, Inc.  
Name & Address: 155 N. Market, Ste. 1010  
Wichita, KS 67202

Lease Name Josserand Well # 1-A  
County Pratt  
Well Total Depth 4400 143.00 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 10 3/4 feet 370

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Duke Drilling Co., Inc. License Number 5929  
Address 310 W. Central, Wichita, KS 67202

Company to plug at: Hour: 3 p.m. Day: 10 Month: 4 Year: 1995

Plugging proposal received from Joe  
(company name) Duke Drilling Co., Inc. (phone) 316-267-1331

work: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 640-665'  
1st plug at 630' with 50 sx cement, 2nd plug at 400' with 75 sx cement,  
3rd plug at 40' with 15 sx cement,  
4th plug to circulate rathole with 15 sx cement,  
5th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Duane Rankin  
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 4:15 p.m. Day: 10 Month: 4 Year: 1995

ACTUAL PLUGGING REPORT 1st plug at 655' with 50 sx cement,  
2nd plug at 400' with 75 sx cement,  
3rd plug at 40' with 15 sx cement,  
4th plug to circulate rathole with 15 sx cement,  
5th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.  
(If additional description is necessary, use BACK of this form.)

RECEIVED  
STATE CORPORATION COMMISSION  
APR 14 1995  
CONSERVATION DIVISION  
WICHITA, KANSAS

INVOICED observe this plugging.

DATE 4-25-95

Signed Steph...  
(TECHNICIAN)

INV. NO. 42687  
4-10 JUN 21 1995