

To: 1 120677
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

2-6
API NUMBER 15- 151-22,076 00-00 62
SW NE NW, SEC. 26, T. 27 S, R 12 W/E R

TECHNICIAN'S PLUGGING REPORT

Operator License # 30395
Operator: Iannitti Oil Company
Name & Address P.O. Box 308
Great Bend, KS 67530

990 feet from NXX section line
1650 feet from WXX section line
Lease Name Barker Well # 1
County Pratt 129.41
Well Total Depth 3982 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 10 3/4 feet 347

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X
Other well as hereinafter indicated _____

Plugging Contractor Woodman-Iannitti Drilling Company License Number 5122
Address P.O. Box 308, Great Bend, KS 67530

Company to plug at: Hour: 6 p.m. Day: 6 Month: 2 Year: 19 92

Plugging proposal received from Rich Wheeler
(company name) Woodman-Iannitti Drilling Company (phone) 316-792-2921

work: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 548-62'
1st plug at 570' with 60 sx cement, 2nd plug at 360' with 75 sx cement,
3rd plug at 40' with 15 sx cement, 4th plug to circulate rathole with 15 sx cement,
5th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Duane Rankin
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 8 p.m. Day: 6 Month: 2 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug at 570' with 1 sx hulls and 60 sx cement,
2nd plug at 360' with 75 sx cement,
3rd plug at 40' with 15 sx cement,
4th plug to circulate rathole with 15 sx cement,
5th plug to circulate mousehole with 10 sx cement.

STATE CORPORATION COMMISSION
FEB 11 1992
CONSERVATION DIVISION
WICHITA, KANSAS

Water well plugged with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel 1/4# Floseal by B.J. Services.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 3-5-92
INV. NO. 34673

Signed Duane Rankin
(TECHNICIAN)