

1 060606

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 151-21,613 - 00-00

SW NE SW , SEC. 26 , T 27 S, R 12 (W) E

1650 feet from S section line

3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5141

Lease Name Barker Well # 1

Operator: Zenith Drilling Corporation

County Pratt 134.33

Name & Address 505 Fourth Financial Center

(Mississippi) Well Total Depth 4133 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 13 3/8 feet 252

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Sterling Drilling Co. License Number 5142

Address Box 129, Sterling, KS 67579

Company to plug at: Hour: 10:00 pm Day: 3 Month: July Year: 19 85

Plugging proposal received from Tom Myers

(company name) Sterling (phone) 316-278-2131

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 1745 KB
Anhydrite 600-610'

1st plug at 870' with 50 sx cement

2nd plug at 270' with 60 sx cement
solid bridge

3rd plug hulls - plug at 40' -- cement to surface with 20 sx cement

5th plug to circulate rat hole with 15 sx cement

Plugging Proposal Received by Paul A. Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 1:30 am Day: 4 Month: July Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 870' with 50 sx cement, 2nd plug at 270' with 60 sx
cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface with
20 sx cement, 5th plug to circulate rathole with 15 sx cement

RECEIVED
STATE CORPORATION COMMISSION

JUL 17 1985

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. (If additional description is necessary, use BACK of this form.)
Wichita, Kansas

UNPLUGGED (did not) observe this plugging.

DATE 7-17-85

INV. NO. 8983

Signed Paul A. Luthi
(TECHNICIAN)