

1 050434

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 151-21,542-60 *R*

NE SW SE , SEC. 24 , T 27 S, R 12 W/E

990 feet from S section line

1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9092

Lease Name Carver Well # 1

Operator: Mallonee-Warren, Ltd.

County Pratt 147.55

Name & Address 302 North Rock Road, Suite 206

Well Total Depth 4540 feet

Wichita, KS 67206

Conductor Pipe: Size feet

Surface Casing: Size 13 3/8 feet 291

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Wheatstate Oilfield Services License Number 5149

Address P. O. Box 329, Pratt, KS 67124

Company to plug at: Hour: 3:30 pm Day: 14 Month: January Year: 19 85

Plugging proposal received from Dennis Petz

(company name) Wheatstate (phone) 316-672-7514

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 660' with 40 sx cement RECEIVED STATE CORPORATION COMMISSION

2nd plug at 330' with 50 sx cement solid bridge JAN 23 1985

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement CONSERVATION DIVISION

5th plug to circulate rat hole with 10 sx cement Wichita, Kansas

6th plug to circulate mouse hole with 10 sx cement Plugging Proposal Received by Richard W. Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All 7 Part None x

Operations Completed: Hour: 5:45 pm Day: 14 Month: January Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 660' with 40 sx cement; 2nd plug at 330' with 50 sx cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface with 10 sx cement. 5th plug to circulate rat hole with 10 sx cement, 6th plug to circulate mouse hole with 10 sx cement.

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Halliburton (If additional description is necessary, use BACK of this form.)

INVOICE (1-28-85) observe this plugging.

DATE INV. NO. 6689

Signed Richard W. Lacey (TECHNICIAN)

FEB 18 1985