

1 050646

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 151-21,704 -00-00

C N/2 SW NW, SEC. 23, T 27 S, R 12 W/E
3630 feet from S section line
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6408

Lease Name Studer Well # 1-G

Operator: W. K. Black, Inc.

County Pratt 148.85

Name & Address P. O. Box 801

Well Total Depth 4580 Arbuckle feet

Pratt, KS 67124

Conductor Pipe: Size _____ feet

Surface Casing: Size 10 3/4 feet 240

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Aldebaran Drilling Co., Inc. License Number 5829

Address Box 18611, Wichita, KS 67207

Company to plug at: Hour: 5:00 am Day: 24 Month: October Year: 19 85

Plugging proposal received from Larry Harris

(company name) Aldebaran (phone) 316-685-5372

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 1806' Anhydrite 590'

1st plug in the Arbuckle with 50 sx cement if in 50' or more

2nd plug at the base of the Anhydrite with 50 sx cement

3rd plug 30' below the base of the surface pipe with 40 sx cement solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 10 sx cement, 7th plug to circulate mouse hole with 10 sx cement. Plug water well with 10 sx cement Plugging Proposal Received by Richard W. Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 7:00 am Day: 24 Month: October Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 4490' with 50 sx cement, 2nd plug at 590' with 50 sx cement, 3rd plug at 290' with 40 sx cement, 4th & 5th plugs - solid bridge - hulls - plug at 40' -- cement to surface with 10 sx cement. 6th plug to circulate rat hole with 10 sx cement, 7th plug to icruclate mouse hole with 10 sx cement. Plugged water well with 10 sx cement.

RECEIVED STATE CORPORATION COMMISS

Remarks: Used 60/40 Pozmix 6% gel by Halliburton (If additional description is necessary, use BACK of this form.)

OCT 28 1985

CONSERVATION DIVISION Wichita, Kansas

INVOICED

observe this plugging.

Signed Richard W. Lacey (TECHNICIAN) R.W.L.

DATE OCT 29 1985

INV. NO. 10766