

1 120222

3-2

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 151-20,400 -00-00

NW SE NW SEC. 21 , T 27 S, R 12 W/EX

3630 feet from S section line

3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9882

Lease Name Maas Well # B-1

Operator: Leasing & Development, Inc.

County Pratt 8938

Name & Address 120 South Market, Suite 501

Well Total Depth 2750 feet

Address 120 South Market, Suite 501

Conductor Pipe: Size \_\_\_\_\_ feet

Wichita, KS 67202

Surface Casing: Size 8 5/8 feet 285

Abandoned Oil Well \_\_\_\_\_ Gas Well  Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Great Bend Casing Pullers, Inc. License Number 4635

Address Box 768, Great Bend, KS 67530

Company to plug at: Hour: 11 a.m. Day: 2 Month: 3 Year: 19 89

Plugging proposal received from Gary Burke

(company name) Great Bend Casing Pullers, Inc. (phone) 316-793-9711

were: 4 1/2" at 2749' Perfs at 2693-2710'

1st plug sand back to 2650' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 100 sx cement.

Plugging Proposal Received by Duane Rankin (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 12:30 P.M. Day: 2 Month: 3 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug sanded 4 1/2" casing back to 2650' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped into 8 5/8" surface casing with 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Pumping pressure 0-200 psi and shut in 0-not on vacuum.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1522' of 4 1/2" casing.

(if additional description is necessary, use BACK of this

RECEIVED STATE CORPORATION COMMISSION

MAR 08 1989

CONSERVATION DIVISION Wichita Kansas

INVOICED (if applicable) observe this plugging.

Signed Duane Rankin (TECHNICIAN)

DATE 3-16-89

INV. NO. 24123