

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-207-02724-00-00
Spot: SWSESWSE Sec/Twnshp/Rge: 14-26S-14E
158 feet from S Section Line, 1663 feet from E Section Line
Lease Name: ALLEN Well #: 1
County: WOODSON Total Vertical Depth: 1296 feet

Operator License No.: 5150
Op Name: COLT ENERGY INC
Address: PO BOX 388
IOLA, KS 66749

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	1278		0 SX
SURF	6.25	20		0 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/11/2014 2:30 PM
Plug Co. License No.: 5150 Plug Co. Name: COLT ENERGY INC
Proposal Rcvd. from: REX ASHLOCK Company: _____ Phone: () 620-3651

Proposed Plugging Method: COMPANY SERVICE UNIT RIH 2" TBG TO BOTTOM SERVICE COMPANY HOOK ON 2" CIRCULATED GEL TO SURFACE. PUMP 300' CEMENT PLUG ON BTM COMPANY SERVICE UNIT PULLED TBG UP TO 500' SERVICE COMPANY PUMP 50' CMT PLUG AT 500'. COMPANY SERVICE UNIT PULL TBG UP TO 250' SERVICE COMPANY PUMPED CEMENT FROM 250' TO SURFACE. COMPANY SERVICE UNIT PULLED REST OF TBG. SERVICE COMPANY TOPPED WELL OFF - HOOKED TO CSG PRESSURE UP SHUT WELL IN. WILL COME BACK AT A LATER TIME & CUT SURFACE OFF "BELOW FLOW DEPTH"

Plugging Proposal Received By: MICHAEL HEFFERN WitnessType: NONE
Date/Time Plugging Completed: 08/11/2014 4:30 PM KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

ran tubing to 1275' pumped 300' cement plug, pulled tubing to 500' pumped 50' cement plug, pulled tubing to 251' circ. Cement to surface, gel spacers between cement plugs

Perfs:

Top	Bot	Thru	Comments
1257	1272		
RECEIVED OCT 20 2014 KCC Chanute Dist #3 MH Received KANSAS CORPORATION COMMISSION			

Remarks:

Plugged through: TBG

OCT 23 2014

CONSERVATION DIVISION
WICHITA, KS

District: 03

Signed Michael Heffern
(TECHNICIAN)

10/29/14 CKM