

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-207-23674-00-00
Spot: SESESWSE Sec/Twnshp/Rge: 14-26S-14E
59 feet from S Section Line, 1505 feet from E Section Line
Lease Name: ALLEN Well #: 2A
County: WOODSON Total Vertical Depth: 1299 feet

Operator License No.: 5150
Op Name: COLT ENERGY INC
Address: PO BOX 388
IOLA, KS 66749

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	1294		175 SX
SURF	8.625	50		25 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/07/2014 12:00 AM
Plug Co. License No.: 5150 Plug Co. Name: COLT ENERGY INC
Proposal Rcvd. from: RICK RICE Company: _____ Phone: (620) 365-3111

Proposed Plugging Method: COMPANY SERVICE UNIT RIH 2" TBG TO BOTTOM. SERVICE COMPANY HOOK ON 2" CIRCULATED GEL TO SURFACE. PUMP 300' CMT PLUG ON BOTTOM COMPANY SERVICE UNIT PULL TBG UP TO 500' SERVICE COMPANY PUMP 50' CEMENT PLUG AT 500' COMPANY SERVICE UNIT PULL TBG IUP TO 250' SERVICE COMPANY PUMPED CEMENT FROM 250' TO SURFACE. COMPANY SERVICE UNIT PULLED REST OF TBG. SERVICE COMPANY TOPPED WELL OFF HOOKED TO CSG PRESSURED UP SHUT WELL IN. WILL COME BACK AT A LATER DATE & CUT SURFACE OFF "BELOW PLOW DEPTH".

Plugging Proposal Received By: MICHAEL HEFFERN WitnessType: NONE
Date/Time Plugging Completed: 08/11/2014 12:00 AM KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

ran tubing to 1299' pumped 300' cement plug, pulled tubing to 500' pumped 50' cement plug, pulled tubing to 250' circ. Cement to surface, gel spacers between cement plugs.

Perfs:

Top	Bot	Thru	Comments
1244	1258		

RECEIVED

OCT 20 2014

KCC Chanute Dist. #3

MH

Received
KANSAS CORPORATION COMMISSION

Remarks:

Plugged through: TBG

OCT 23 2014

CONSERVATION DIVISION
WICHITA, KS

District: 03

Signed Mike D. Jensen
(TECHNICIAN)

10/29/14 CKM