

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-20453-00-00
Spot: E2SENE Sec/Twnshp/Rge: 18-30S-9W
1980 feet from N Section Line, 330 feet from E Section Line
Lease Name: GOETZ Well #: 1
County: KINGMAN Total Vertical Depth: 4355 feet

Operator License No.: 30931
Op Name: DAYSTAR PETROLEUM, INC.
Address: 522 N. MAIN ST PO BOX 560
EUREKA, KS 67045

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4332		200 SX
SURF	8.625	264		250 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 08/25/2014 12:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: DAYSTAR PETROLEUM, IN Company: MIKES TESTING & SALVAGE Phone: (620) 583-5527

Proposed Plugging Method: BP 4300' & 4 SXS. 35 SXS @ 1450, 35 SXS @ 1000'. CIRC 310' TO 0'.

Plugging Proposal Received By: _____ WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/30/2014 10:00 AM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

SET CIBP @ 4300' & 4 SXS CEMENT. O' RECOVERY. PERF 1450', 1000', 310'. RAN PAKER TO 1250', SET PAKER PUMEPD 35 SXS CEMENT - CIRCULATED THE WELL UP 1000' & 310'. FRESH WATER COMING UP 310' PERF. PULLED PAKER TO 850', PUMPED 35 SXS CEMENT. FRESH WATER UP 310; PERFS WAITED 2 HOURS. COULD NOT TAG ANY CEMENT INSIDE 4 1/2". RAN TUBING TO 1400' PUMPED 135 SXS CEMENT. CIRC CEMENT UP INSIDE OF 4 1/2" & ANNULUAS. LET SET OVER WEEKEND. CUT OFF HEAD, FOUND CEMENT 125' ON BACKSIDE & 250' IN ANNULAS. PUMPED 50 SXS CEMENT DOWN 4 1/2" & DOWN ANNULUS, FILL TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
4332	4355	OH	

Remarks:

Plugged through:

District: 02

Signed _____

10/29/14 ckm

(TECHNICIAN)
Received
KANSAS CORPORATION COMMISSION

OCT 23 2014

CONSERVATION DIVISION
WICHITA, KS