

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-191-22156-00-00
Spot: SENWSW Sec/Twnshp/Rge: 3-35S-1E
1485 feet from S Section Line, 4125 feet from E Section Line
Lease Name: BATES Well #: 12
County: SUMNER Total Vertical Depth: 4639 feet

Operator License No.: 30931
Op Name: DAYSTAR PETROLEUM, INC.
Address: 522 N. MAIN ST PO BOX 560
EUREKA, KS 67045

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| PROD | 5.5 | 3989 | 1500 | 500 SX |
| SURF | 8.625 | 262 | | 175 SX |

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/10/2014 11:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO/NATHAN WO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 562-8088

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DAN FOX WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/20/2014 11:30 AM KCC Agent: DAN FOX

Actual Plugging Report:

THERE ARE SEVERAL CIBP'S IN THIS WELL, 3770', 3685', 3350', AND 2890' TOP CIBP SET AT 2800' W/2 SXS CAP. OPERATOR SHOT OFF 5 1/2" AT THE NEXT JOINT UP AND PULLED 1,500', THEN PERFORATED AT 312' AND CIRCULATE BACKSIDE TO SURFACE. 60/40 POS MIX WITH 4% GEL. CONSOLIDATED OUT OF EUREKA TICKET #42779. SHOT & PULLED 1,500' OF 5 1/2" CASING.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 2852 | 2857 | TBG | |

Remarks: NATHAN WOOD W/MIKE'S TESTING WAS ON SITE. HIS NUMBER IS 620-617-1213.

Plugged through: TBG

District: 02

Signed _____

10/29/14 CKM

(TECHNICIAN)

Received
KANSAS CORPORATION COMMISSION

OCT 23 2014

Form CP-2/3

CONSERVATION DIVISION
WICHITA, KS