

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-093-21930-00-00  
Spot: NWSEENW Sec/Twnshp/Rge: 33-21S-36W  
874 feet from N Section Line, 2266 feet from W Section Line  
Lease Name: MURRAY Well #: 1-33  
County: KEARNY Total Vertical Depth: 5026 feet

Operator License No.: 30535  
Op Name: HARTMAN OIL CO., INC.  
Address: 10500 E BERKELEY SQ PKWY STE 100  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	355		WITH 225 SX CMT

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/16/2014 3:45 AM  
Plug Co. License No.: 33793 Plug Co. Name: H2 DRILLING LLC  
Proposal Rcvd. from: CARLOS FABELA Company: H2 DRILLING LLC Phone: (316) 636-2090

Proposed Plugging Method: 1ST PLUG AT 2280' WITH 50 SX CMT. 2ND PLUG AT 1080' WITH 80 SX CMT. 3RD PLUG AT 390' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN Witness Type: NONE  
Date/Time Plugging Completed: 10/16/2014 5:45 AM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

Perfs:

1ST PLUG AT 2280' WITH 50 SX CMT. 2ND PLUG AT 1080' WITH 80 SX CMT. 3RD PLUG AT 390' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Received  
KANSAS CORPORATION COMMISSION

OCT 29 2014

CONSERVATION DIVISION  
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY ALLIED.

Plugged through: DP

District: 01

Signed



10/29/14

(TECHNICIAN)

RECEIVED

OCT 22 2014

KCC DODGE CITY



Form CP-2/3