

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-155-20369-00-00
Spot: NESWNE Sec/Twnshp/Rge: 5-25S-5W
3630 feet from S Section Line, 1650 feet from E Section Line
Lease Name: KRANZ Well #: 1
County: RENO Total Vertical Depth: 3591 feet

Operator License No.: 3273
Op Name: HERMAN L. LOEB, LLC
Address: PO BOX 838
LAWRENCEVILLE, IL 62439

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3588	1192	250 SX
SURF	8.625	260		250 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 10/07/2014 12:00 AM
Plug Co. License No.: 32983 Plug Co. Name: STEVE'S WELL SERVICE, INC.
Proposal Rcvd. from: TRACY BLACK Company: STEVE'S WELL SERVICE Phone: (316) 215-1873

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: B. J. HOPE Witness Type: PARTIAL
Date/Time Plugging Completed: 10/07/2014 4:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

SET CIBP @ 3486 CAPPED WITH 2 SXS CEMENT ON TOP. CUT CASING PIPE OFF @ 1192'. RAN TUBING INTO 837' SPOTTED 50 SXS COMMON CEMENT W/3% CC. WAITED 2 HOURS TAGGED TOC @ 720'. RAN TUBING INTO 320' CIRCUALTED TO SURFACE WITH 150 SXS CEMENT.

Perfs:

Top	Bot	Thru	Comments
3486	3496		
..			..

Received
KANSAS CORPORATION COMMISSION
OCT 28 2014
CONSERVATION DIVISION
WICHITA, KS

Remarks: COPELAND CEMENTING OUT OF GREAT BEND, COMMON CEMENT, TICKET #

Plugged through: TBG

District: 02

Signed Bj Hope
CKM 10/29/14 (TECHNICIAN)