

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-151-19011-00-00
Spot: SESESE Sec/Twnshp/Rge: 12-27S-13W
343 feet from S Section Line, 470 feet from E Section Line
Lease Name: SICU Well #: 4
County: PRATT Total Vertical Depth: 4322 feet

Operator License No.: 31739
Op Name: IUKA-CARMI DEVELOPMENT LLC
Address: PO BOX 847
PRATT, KS 67124

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|-----------------|
| CIBP | | 4070 | | WITH 2 SX CMT |
| PROD | 5.5 | 4322 | 0 | WITH 200 SX CMT |
| SURF | 8.625 | 731 | | WITH 450 SX CMT |

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 10/15/2014 2:30 PM
Plug Co. License No.: 5893 Plug Co. Name: PRATT WELL SERVICE, INC.
Proposal Rcvd. from: GARELD INSLEE Company: PRATT WELL SERVICE, INC. Phone: (620) 672-2531

Proposed Plugging Method: CIBP 50' ABOVE PERFS & 2 SX CMT. LOAD HOLE. TEST CASING. PERFORATE CASING AT 760' & CIRCULATE CM TO SURFACE.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/15/2014 3:51 PM KCC Agent: ROBERT DICKERSON

Actual Plugging Report:

SET CIBP @ 4070' WITH 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. PERFORATED AT 745'. PUMP DOWN 5 1/2" CASING WITH 200 SX CMT. CMT CIRCULATED TO SURFACE.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 4203 | 4315 | | |

Received
KANSAS CORPORATION COMMISSION
OCT 29 2014
CONSERVATION DIVISION
WICHITA, KS

Remarks: **COMPLIANCE ISSUE: DENIED TA SI 10 YRS** USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: CSG

District: 01

Signed

Robert Dickerson
10/29/14 OCM (TECHNICIAN)
SR

RECEIVED
OCT 21 2014
KCC DODGE CITY