

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-151-22223-00-00
Spot: SESW Sec/Twnshp/Rge: 25-26S-11W
680 feet from S Section Line, 1967 feet from W Section Line
Lease Name: MILTON Well #: 1
County: PRATT Total Vertical Depth: 4363 feet

Operator License No.: 6039
Op Name: L. D. DRILLING, INC.
Address: 7 SW 26TH AVE
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4250		
PROD	5.5	4362	1906	WITH 175 SX CMT
SURF	8.625	479		WITH 375 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/14/2014 10:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: JAMIE HARRIS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2943

Proposed Plugging Method: CIBP @ 4250' WITH 2 SX CMT. PLUG AT 710' WITH 10 SX GEL & 40 SX CMT. PLUG AT 520' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/14/2014 11:35 AM KCC Agent: ROBERT DICKERSON

Actual Plugging Report:

SET CIBP @ 4250' WITH 2 SX CMT ON TOP CIBP THROUGH DUMP BAILER. 1ST PLUG AT 700' WITH 10 SX GEL & 40 SX CMT. 2ND PLUG AT 520' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4300	4303		

Received
KANSAS CORPORATION COMMISSION

OCT-29-2014

CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL COPELAND ACID & CEMENT.

Plugged through: CSG

District: 01

Signed

Robert Dickerson
10/29/14 CKM (TECHNICIAN)

RECEIVED

OCT 21 2014

KCC DODGE CITY

Form CP-2/3