

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-155-21701-00-00
Spot: NWNWNE Sec/Twnshp/Rge: 15-23S-10W
330 feet from N Section Line, 2310 feet from E Section Line
Lease Name: WITHRODER Well #: 1
County: RENO Total Vertical Depth: 3850 feet

Operator License No.: 31714
Op Name: NOVY OIL & GAS, INC.
Address: PO BOX 559
GODDARD, KS 67052

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3850	1200	100 SX
SURF	8.625	257		160 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/18/2014 12:00 AM
Plug Co. License No.: 6454 Plug Co. Name: CHEYENNE WELL SERVICE, INC.
Proposal Rcvd. from: HAL HOSS Company: CHEYENNE WELL SERVICE Phone: (620) 282-2212

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: VIRGIL CLOTHIER Witness Type: PARTIAL
Date/Time Plugging Completed: 09/27/2014 4:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

SANDED BACK TO 3698' TRIED TO DUMP 40' BRASS BAILER, STUCK BAILER @ 3600' WIRELINE PULLED OUT OF HEAD WITH 5000 LBS. LEAVING BAILER FULL OF CEMENT. CUT CASING PIPE OFF @ 1200' SPOTTED 45 SXS CEMENT. PULLED CASING TO 900' SPOTTED 35 SXS CEMENT. PULLED CASING TO 310' CIRCUALTED TO SURFACE WITH 175 SXS CEMENT. 10-6-14 CHECK SURFACE, CEMENT FELL BACK 65'. TOPPED OFF WITH 14 SXS OF CEMENT.

Perfs:

Top	Bot	Thru	Comments
3798	3802		

Received
KANSAS CORPORATION COMMISSION
OCT 28 2014
CONSERVATION DIVISION
WICHITA, KS

Remarks: ALLIED CEMENTING OUT OF GREAT BEND, COMMON CEMENT, TICKET #063926

Plugged through: CSG

District: 02

Signed B. J. Hope
10/29/14 ckm (TECHNICIAN)