

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-119-20096-00-00
Spot: SENW Sec/Twnshp/Rge: 14-35S-29W
591 feet from S Section Line, 1845 feet from W Section Line
Lease Name: ADAMS RANCH Well #: D-5
County: MEADE Total Vertical Depth: 6365 feet

Operator License No.: 34399
Op Name: QUANTUM RESOURCES MANAGEMEN
Address: 1401 MCKINNEY ST, STE 2400
HOUSTON, TX 77010

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5861		WITH 2 SX CMT
CIBP		6094		
PROD	4.5	6275	2315	WITH 300 SX CMT
SURF	8.625	1568		WITH 675 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 10/16/2014 11:00 AM
Plug Co. License No.: 32833 Plug Co. Name: SARGENT LILLARD CASING PULLING, INC.
Proposal Rcvd. from: KIRBY LILLARD Company: SARGENT LILLARD CASING PULL Phone: (580) 254-1881

Proposed Plugging Method: SET CIBP @ 5861' WITH 2 SX CMT. PLUG AT 1600' WITH 50 SX CMT. PLUG AT 450' WITH 40 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN Witness Type: PARTIAL
Date/Time Plugging Completed: 10/16/2014 4:00 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SET CIBP @ 5861' WITH 2 SX CMT. LOADED HOLE WITH MUD. 1ST PLUG AT 1600' WITH 50 SX CMT. 2ND PLUG AT 450' WITH 40 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
6109	6230		
5911	6081		

Received
KANSAS CORPORATION COMMISSION
OCT 29 2014
CONSERVATION DIVISION
WICHITA, KS

Remarks: **COMPLIANCE ISSUE: DENIED TA SI 10 YRS** USED COMMON CEMEBNT BY SARGENT LILLARD.

Plugged through: CSG

District: 01

Signed Eric McClaren
10/29/14 (TECHNICIAN)

RECEIVED
OCT 21 2014
KCC DODGE CITY