

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-187-00306-00-03
Spot: SE Sec/Twnshp/Rge: 23-30S-43W
1335 feet from S Section Line, 1308 feet from E Section Line
Lease Name: HUME Well #: 1-23
County: STANTON Total Vertical Depth: 5402 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: 3118 CUMMINGS RD PO BOX 399
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4960		
COND	16	134		WITH 370 SX CMT
PROD	4.5	5402	2527	WITH 125 SX CMT
SURF	8.625	1511		WITH 800 SX CMT

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 10/14/2014 10:00 AM
Plug Co. License No.: 32833 Plug Co. Name: SARGENT LILLARD CASING PULLING, INC.
Proposal Rcvd. from: JOHN SCHOOLCRAFT Company: SARGENT LILLARD CASING PULL Phone: (580) 254-1881

Proposed Plugging Method: SET CIBP @ 5208' WITH 2 SX CMT. PLUG AT 1540' WITH 50 SX CMT. PLUG AT 550' WITH 40 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/14/2014 5:00 PM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

RUNNING IN HOLE WITH JUNK BAR COULDN'T GET PAST 4614'. OK'D TO PUT CIBP THERE. RAN IN WITH CIBP & GOT TO 4960' & SET IT. COULDN'T GET CMT BAILER PAST 4614'. HOLE WAS FULL OF FLUID PREVENTING A WAY TO GET CMT ON CIBP. 1ST PLUG AT 1540' WITH 50 SX CMT. 2ND PLUG AT 550' WITH 40 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5258	5336		

Received
KANSAS CORPORATION COMMISSION
OCT 29 2014
CONSERVATION DIVISION
WICHITA, KS

Remarks: **COMPLIANCE ISSUE: DENIED TA SI 10 YRS** USED COMMON CEMENT BY SARGENT LILLARD.

Plugged through: CSG

District: 01

RECEIVED
OCT 21 2014
KCC DODGE CITY

Signed [Signature]
10/29/14 CKM (TECHNICIAN)