

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-083-20585-00-00  
Spot: SWNW Sec/Twnshp/Rge: 10-23S-22W  
3318 feet from S Section Line, 4598 feet from E Section Line  
Lease Name: QUERBACH Well #: 2  
County: HODGEMAN Total Vertical Depth: 4457 feet

Operator License No.: 32331  
Op Name: DK OPERATING INC.  
Address: 621 BENTON ST.  
JETMORE, KS 67854

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4400		WITH 2 SX CMT
DVT	4.5	1303		CEMENTED TO SURFACE
PROD	4.5	4452	0	WITH 425 SX CMT
SURF	8.625	371		WITH 225 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/15/2014 9:00 AM  
Plug Co. License No.: 6454 Plug Co. Name: CHEYENNE WELL SERVICE, INC.  
Proposal Rcvd. from: HAL HOSS Company: CHEYENNE WELL SERVICE, INC. Phone: (785) 798-5051

Proposed Plugging Method: SET CIBP AT 4400' WITH 2 SXC MT. LOAD HOLE WITH FLUID & RUN BOND LOG. IF NOT CMT ON TOP PERFORATE & CIRCULATE TO SURFACE.

Plugging Proposal Received By: STEVE PFEIFER Witness Type: PARTIAL  
Date/Time Plugging Completed: 10/16/2014 11:00 AM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

SET CIBP @ 4400' WITH 2 SX CMT. RAN BOND LOG 1400' TO SURFACE. FOUND CMT ALL THE WAY UP TO SURFACE FROM 1303'. RUN TBG TO 1350' & PUMPED 90 SX CMT. LOST CIRCULATION. SDON. 10/16/14: RUN IN SAND LINE & FOUND CMT AT 1650'. LOADED HOLE & STAYED FULL. RUN TBG TO 1350' & PUMPED 90 SX CMT. CMT CIRCULATED. PULLED TBG & TOPPED OFF WITH 10 SX CMT. TIED ONTO BACKSIDE & COULDN'T PUMP IN TO.

Perfs:

Top	Bot	Thru	Comments
4452	4457	OH	

Received  
KANSAS CORPORATION COMMISSION

OCT-29-2014

CONSERVATION DIVISION  
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

RECEIVED  
OCT 21 2014  
KCC DODGE CITY

Signed Michael Maier  
(TECHNICIAN)

10/29/14 CEM