

1 120223

3-2

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 151-20,458-00-00
C NE NW, SEC. 28, T 27 S, R 12 W
4620 feet from S section line
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5316

Lease Name Lunt Well # 1

Operator: Falcon Exploration Inc.
Name & Address 125 North Market, Suite 1531
Wichita, KS 67202

County Pratt 88.24
Well Total Depth 2715 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 291

Abandoned Oil Well Gas Well X Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Great Bend Casing Pullers, Inc. License Number 4635

Address Box 768, Great Bend, KS 67530

Company to plug at: Hour: 1 p.m. Day: 2 Month: 3 Year: 19 89

Plugging proposal received from Gary Burke

(company name) Great Bend Casing Pullers, Inc. (phone) 316-793-9711

were: 4 1/2" at 2707' cemented w/100 sx Perfs at 2643-47'
1st plug sand back to 2590' and dump 4 sx cement on top of sand through bailer,
2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"
wiper plug and pump 100 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 2:30 p.m. Day: 2 Month: 3 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug sanded 4 1/2" casing back to 2590' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped into 8 5/8" surface casing with 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, and 100 sx cement.

Pumping pressure 0-400 psi and shut in 200 psi. Welded plate on 8 5/8" casing.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1922' of 4 1/2" casing.

(If additional description is necessary, use BACK of this form.)

observe this plugging.

INVOICED

DATE 3-16-89

Signed [Signature] (TECHNICIAN)

INV. NO. 24121

RECEIVED STATE CORPORATION COMMISSION MAR 08 1989 CONSERVATION DIVISION Wichita Kansas