

10-29-87 15-151-20042-00.00

To: 1 120039
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- NA
NW SW SE, SEC. 35, T 27 S, R 12 W/X
990 feet from S section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5435

2310 feet from E section line

Operator: Bowers Drilling Inc.
Name & Address
125 North Market, Suite 1425
Wichita, KS 67202

Lease Name Barker Well # B-4

County Pratt 133.74

Well Total Depth 4115 feet

Conductor Pipe: Size 13 3/8 feet 215

Surface Casing: Size 8 5/8 feet 316

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Bowers Drilling Inc. License Number 5435

Address 125 North Market, Suite 1424, Wichita, KS 67202

Company to plug at: Hour: 8:45 a.m. Day: 29 Month: 10 Year: 19 87

Plugging proposal received from Bill Musgrove

(company name) Bowers Drilling Inc. (phone) 316-886-5520

were: 4 1/2" at 4104' PBD 3920' Perfs at 3659-3972' (6 sets)

1st plug sand back to 3600' and dump 4 sx cement on top of sand through bailer,
2nd plug pump 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"
wiper plug and pump 130 sx cement.

Plugging Proposal Received by Paul Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 9 a.m. Day: 29 Month: 10 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug sanded back to 3600' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped into 8 5/8" surface casing with 400 lbs. hulls and 100 sx white cement.

Checked plug 10/30/87. Down 78'. Filled with 1 yd. Ready Mix.

Pumping pressure 450 psi and shut-in 300 psi.

Remarks: Used Thrifty Mix cement by B.J. Titan. Recovered 1250' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED
I did not observe this plugging.

DATE 11-9-87

INV. NO. 18754

Signed Duane Rankin (TECHNICIAN)

STATE CORPORATION COMMISSION
NOV 5 1987
CONSERVATION DIVISION
WICHITA, KANSAS