

10-29-87

1 040001

API NUMBER 15- Docket #E-14,279

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

C N/2 S/2 SE, SEC. 35, T 27 S, R 12 W/E

990 feet from S section line

1320 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5435

Lease Name Barker Well # B-2

Operator: Bowers Drilling Inc.

County Pratt 133.90

Name & Address 125 North Market, Suite 1425

Well Total Depth 4120 feet

Wichita, KS 67202

Conductor Pipe: Size 13 3/8 feet 100

Surface Casing: Size 8 5/8 feet 838

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well X SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Bowers Drilling Inc. License Number 5435

Address 125 North Market, Suite 1425, Wichita, KS 67202

Company to plug at: Hour: 9:30 a.m. Day: 29 Month: 10 Year: 19 87

Plugging proposal received from Bill Musgrove

(company name) Bowers Drilling Inc. (phone) 316-886-5520

were: 5 1/2" at 3977' PBSD 3972' Perfs at 3665-3972' (5 sets) TOC 3060'

1st plug sand back to 3400' and dump 6 sx cement on top of sand through bailer,

2nd plug pump 400 lbs. hulls and 100 sx lite cement.

Plugging Proposal Received by Dan Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 10:15 a.m. Day: 29 Month: 10 Year: 1987

ACTUAL PLUGGING REPORT 1st plug sanded back to 3400' and dumped 6 sx cement on top of sand through bailer.

2nd plug pumped in 8 5/8" surface casing with 400 lbs. hulls and 100 sx lite cement.

Pumping pressure 450 psi and shut in 300 psi.

This well was an injection well. Please cancel the injection order (no other wells on lease).

Remarks: Used Thrifty Mix cement by B.J. Titan. Recovered 1800' of 5 1/2" casing.

(If additional description is necessary, use BACK of this form.)

STATE CORPORATION COMMISSION

INVOICED observe this plugging.

NOV 5 1987

Signed Stephen O. Pfeifer (TECHNICIAN)

DATE 11-9-87

CONSERVATION DIVISION Wichita, Kansas

INV. NO. 18756