

1 010275

8-7-87

15-151-30121-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- N/A

TECHNICIAN'S PLUGGING REPORT

Operator License # 5435

2970 feet from S section line

660 feet from E section line

Lease Name Barker Well # A-1

Operator: Bowers Drilling Company
Name & Address: 125 North Market, Suite 1425
Wichita, KS 67202

County: Pratt 142.68

Well Total Depth 4390 feet

Conductor Pipe: Size 13 3/8 feet 95

Surface Casing: Size 8 5/8 feet 827

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Bowers Drilling Company License Number 5435

Address 125 North Market, Suite 1425, Wichita, KS 67202

Company to plug at: Hour: 9 a.m. Day: 7 Month: 8 Year: 1987

Plugging proposal received from Bill Musgrove

(company name) Bowers Drilling Company (phone) 316-886-5520

were: 4 1/2" at 4012' PBTB 3979' Perfs at 3863-7, 3801-5, 3777, 3902-8, 3942-6, 3889-93'
1st plug sand back to 3650' and dump 4 sx cement on top of sand through bailer,
2nd plug pump 3 sx hulls, 110 sx thrifty mix with 2 sx hulls mixed in.

Plugging Proposal Received by Glenn Barlow & Jack Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 9:40 a.m. Day: 7 Month: 8 Year: 1987

ACTUAL PLUGGING REPORT 1st plug sanded back to 3500' and dumped 4 sx cement on top through
bailer,

2nd plug pumped 3 sx hulls, 110 sx of thrifty mix with 2 sx hulls mixed in.

RECEIVED

STATE CORPORATION COMMISSION

AUG 11 1987

CONSERVATION DIVISION
Wichita, Kansas

Maximum pressure 550 psi and shut in 500 psi.

Remarks: Used Thrifty Mix by B.J. Titan, TOC 3400'. Recovered 2000' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

(If you observe this plugging.)

Signed Jack Luthi (TECHNICIAN)

DATE 8-12-87

INV. NO. 17797

8-7

28