

To: 1 010100
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 151-21,577 - 00-00
NW NE SE, SEC. 34, T. 27 S, R. 12 W/E
2310 feet from S section line
990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9514
Operator: D & D Production, Inc.
Name & Address: P. O. Box 321
Pratt, KS 67124

Lease Name Barker Well # A-1
County Pratt
Well Total Depth 4595 ^{149.34} feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 400

Abandoned Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050
Address P. O. Box 347, Chase, KS 67524

Company to plug at: Hour: 11:10 am Day: 3 Month: March Year: 19 86

Plugging proposal received from Curtis Duntz

(company name) Kelso (phone) 316-938-2457

were: 5 1/2" at 4571' Perfs at 4335-52' plug at 4300'; 4156-66'; plug at 3950'; 3870-72'
plug at 3850'; 3814-16'

1st plug sand back to 3760' and dump 5 sx cement on top of sand through bailer

2nd plug squeeze well with 2 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls,
release 8 5/8" rubber plug and pump 150 sx cement

Plugging Proposal Received by Paul A. Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All y Part _____ None _____

Operations Completed: Hour: 11:35 am Day: 3 Month: March Year: 19 86

ACTUAL PLUGGING REPORT 1st plug sanded back to 3760' and dumped 5 sx cement on top of sand
through bailer, 2nd plug squeezed well with 2 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel,
1 sack hulls, released 8 5/8" rubber plug and pumped 150 sx cement.

Maximum pressure 200 psi and shut in went on vacuum.

Remarks: Recovered 3200' 5 1/2" casing. Used 60/40 Pozmix 6% gel by Allied.
(If additional description is necessary, use BACK of this form.)

I (did / ~~did not~~) observe this plugging. RECEIVED
STATE CORPORATION COMMISSION

INVOICED
DATE MAR 12 1986

MAR 11 1986

Signed Paul A. Luthi
(TECHNICIAN)