

1040891

9-20

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 9408  
Operator: Trans Pacific Oil Corporation  
Name & Address One Main Place, Ste. 1000  
Wichita, KS 67202

API NUMBER 15- 151-20,530-00-00  
C NW NW, SEC. 4, T 27 S, R 13 W/E  
4620 feet from S section line  
4620 feet from E section line  
Lease Name Chance Well # 1  
County Pratt  
Well Total Depth 3350 108.87 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 10 3/4 feet 402

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor D.S. & W. Well Servicing, Inc. License Number 6901  
Address P.O. Box 231, Claflin, KS 67525

Company to plug at: Hour: 1:30 p.m. Day: 20 Month: 9 Year: 19 94

Plugging proposal received from Kevin Strube  
(company name) D.S. & W. Well Servicing, Inc. (phone) 316-587-3361

Work: 4 1/2" at 3322' w/250 sx cement, PBSD 3322', Perfs at 2960-75'  
1st plug sand back to 2900' and dump 4 sx cement on top of sand through bailer,  
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 10 3/4"  
wiper plug and pump 150 sx cement.

Plugging Proposal Received by Steve Middleton  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_  
Operations Completed: Hour: 2:15 p.m. Day: 20 Month: 9 Year: 19 94

ACTUAL PLUGGING REPORT 1st plug sanded back to 2900' and dumped 4 sx cement on top of  
sand bridge through bailer,

2nd plug pumped down 10 3/4" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel,  
200 lbs. hulls and 150 sx cement.

Maximum pressure 200 psi and shut in 25 psi.  
8 5/8" collar welded into 10 3/4" surface pipe.

STATE CORPORATION COMMISSION  
RECEIVED 10 sx  
SEP 23 1994

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2253' of 4 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 10-10-94  
INV. NO. 41390

Signed Stephen J. DePue  
(TECHNICIAN)