

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-151-21636-00-00
Spot: SWNWNW Sec/Twnshp/Rge: 4-27S-13W
4290 feet from S Section Line, 4950 feet from E Section Line
Lease/Unit Name: CHANCE Well Number: 1
County: PRATT Total Vertical Depth: 4452 feet

Operator License No.: 9408
Op Name: TRANS PACIFIC OIL CORPORATION
Address: 100 SOUTH MAIN STE 200
WICHITA, KS 67202

Conductor Pipe: Size 13.375 feet: 254 2144.69
Surface Casing: Size 8.625 feet: 1016 WITH 350 SX CMT
Production: Size 5.5 feet: 4449 WITH 250 SX CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 03/19/2002 1:30 PM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: VERNON PFLUGHOEFT Company: D S & W WELL SERVICING, INC. Phone: (316) 587-3361

Proposed Plugging Method: SAND BACK TO 4400' & 5 SX CMT. 1ST PLUG AT 1040' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 280' WITH 40 SX CMT. 3RD PLUG AT 0-40' WITH 10 SX CMT.

Plugging Proposal Received By: SCOTT ALBERG WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 03/19/2002 3:00 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

PBTD 4423'. OPEN HOLE AT 4449-4455'. SANDED BACK TO 4398' & PUT 5 SX CMT ON TOP OF SAND BRIDGE THROUGH DUMP BAILER. SPOT PLUGS THROUGH 5 1/2" CASING. 1ST PLUG AT 1040' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 280' WITH 40 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Remarks: USED 60/40 POZMIX 6% GEL BY COPELAND ACID & CEMENT. RECOVERED 1825' OF 5 1/2" CASING.

Plugged through: CSG

District: 01

Signed

Stephen J. Pfeifer
(TECHNICIAN)

INVOICED

DATE March 28-02

INV. NO. 2002061580

RECEIVED

MAR 28 2002

KCC WICHITA

MAR 25 2002

MP

[Signature]
Form CP 2/8