

To: 1 080809
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

11-22 API NUMBER 15- 151-20,850-00-00
S/2 NW SE, SEC. 5, T 27 S, R 13 W/R
1650 feet from S section line
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9860
Operator: Castle Resources, Inc.
Name & Address: 1200 E. 27th, #C
Hays, KS 67601

Lease Name Lemon Well # 1
County Pratt
Well Total Depth 4525 147.06 feet
Conductor Pipe: Size feet
Surface Casing: Size 10 3/4 feet 447

Abandoned Oil Well Gas Well Input Well SWD Well D&A
Other well as hereinafter indicated

Plugging Contractor DS&W Well Servicing, Inc. License Number 6901
Address P.O. Box 231, Claflin, KS 67525

Company to plug at: Hour: 2 p.m. Day: 22 Month: 11 Year: 1993

Plugging proposal received from Joe Strube
(company name) DS&W Well Servicing, Inc. (phone) 316-587-3361

were: 4 1/2" at 4502' w/225 sx cement, PBSD 3920', Perfs at 3993-94, 3976-78, 3874-77, 4249-58'
1st plug sand back to 3825' and dump 4 sx cement on top of sand through bailer,
2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release 10 3/4"
wiper plug and pump 150 sx cement.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None
Operations Completed: Hour: 2:45 p.m. Day: 22 Month: 11 Year: 1993

ACTUAL PLUGGING REPORT 1st plug sanded back to 3825' and dumped 4 sx cement on top of sand
bridge through bailer,
2nd plug pumped down 10 3/4" with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs.
hulls, released 10 3/4" wiper plug and pumped 150 sx cement.
Maximum pressure 300 psi and shut in 100 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2523' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 12-3-93
INV. NO. 39322

Signed Stephen J. Pfeifer
(TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
DEC 01 1993
CONSERVATION DIVISION
Wichita, Kansas