

409

7-13

6 061543

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-009-14484-0000

SW, SEC. 7, T 20 S, R 12 W/E

330 feet from S section line

4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5010

Lease Name Schartz Well # 2

Operator: Knighton Oil Co. Inc.

County Barton 111.64

Name & Address 710 Petroleum Bldg.

Well Total Depth 3435 feet

Wichita, Ks. 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 365

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347 Chase, Ks. 67524

Company to plug at: Hour: 9:00AM Day: 13 Month: July Year: 19 88

Plugging proposal received from Mike Kelso

(company name) Kelso Casing Pulling Inc. (phone)

were: Order 125 sks 65/35 Poz 10% Gel 2% Econolite 5 sks Hulls.

RECEIVED
STATE CORPORATION COMMISSION

NOV 8 1988

CONSERVATION DIVISION
Wichita, Kansas

Plugging Proposal Received by Gilbert Scheck (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 11:15AM Day: 13 Month: July Year: 19 88

ACTUAL PLUGGING REPORT 8 5/8" set at 365' w/350 sks. 5 1/2" set at 3433' w/150sks.

Top perf at 3174'. Plugged bottom w/sand and 5 sks cement to 3125'. Shot pipe

five times and recovered 405'. Pumped in 8 5/8" 25 sks cement followed w/5 sks

Hulls in 100 sks cement w/ 900 psi.

Well had been squeezed at 500'. Shot holes at 2400' -2000' 1500' 1000' and 405'

Remarks: Allied.
(If additional description is necessary, use BACK of this form.)

INVOICED
If (old / correct) observe this plugging.

Signed 
Gilbert G. Scheck (TECHNICIAN)

DATE 11-9-88

INV. NO. 22961