

7-13

6 061545

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-009-14486-0000
SW, SEC. 7, T 20 S, R 12 W/4E

TECHNICIAN'S PLUGGING REPORT

Operator License # 5010

660 feet from S section line
3630 feet from E section line

Operator: Knighton Oil Co. Inc.
Name & Address: 710 Petroleum Bldg.
Wichita, Ks. 67202

Lease Name Schartz Well # 4
County Barton 112.29

Well Total Depth 3455 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 370

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ U&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling Inc. License Number 6050

Address Box 347 Chase, Ks. 67524

Company to plug at: Hour: 9:00AM Day: 13 Month: July Year: 19 88

Plugging proposal received from Mike Kelso

(company name) Kelso Casing Pulling Inc. (phone) _____

were: Order 125 sks 65/35 Poz 10% Gel 2% Econolite 5 sks Hulls.

RECEIVED
STATE CORPORATION COMMISSION

OCT 21 1988

CONSERVATION DIVISION
Wichita, Kansas

Plugging Proposal Received by Gilbert G. Scheck
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:30PM Day: 13 Month: July Year: 19 88

ACTUAL PLUGGING REPORT 8 5/8" set at 370' w/350 sks. 5 1/2" set at 3453' w/150 sks.

Top perf at 3158'. Plugged bottom w/sand and 5 sks cement to 3100'. Shot pipe two times and recovered 2467'. Pumped in 8 5/8" 25 sks cement followed w/5 sks Hulls in 100 sks cement w/800 psi.

Remarks: By Allied
(If additional description is necessary, use BACK of this form.)

INVOICED
I (did/ did not) observe this plugging.

DATE 10-25-88

Signed *Gilbert G. Scheck*
(TECHNICIAN)
Gilbert G. Scheck

INV. NO. 22698