

7-13

To: 6 061542
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 009-14483 -0000
SW _____, SEC. 7, T 20 S, R 12 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 5010
Operator: Knighton Oil Co. Inc.
Name & Address: 710 Petroleum Bldg
Wichita, Ks. 67202

330 feet from S section line
2970 feet from E section line
Lease Name Schartz Well # 1
County Barton 122.06
Well Total Depth 3448 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 366

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling Inc. License Number 6050

Address Box 347 Chase, Ks. 67524

Company to plug at: Hour: 9:00 AM Day: 13 Month: July Year: 19 88

Plugging proposal received from Mike Kelso

(company name) Kelso Casing Pulling Inc. (phone) _____

were: Order 125 sks 65/35 Poz 10% Gel 2% Econolite 5 sks Hulls.

RECEIVED
STATE CORPORATION COMMISSION
OCT 21 1988
10-21-88

CONSERVATION DIVISION
Wichita, Kansas

Plugging Proposal Received by Gilbert G. Scheck (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10:30AM Day: 13 Month: July Year: 19 88

ACTUAL PLUGGING REPORT 8 5/8" set at 366' w/350 sks. 5 1/2" set at

3270' w/150 sks. Top perf at 3175'. Plugged bottom w/sand and 5 sks

cement to 3125'. Shot pipe one time and recovered 2450'. Pumped in 8 5/8"

25 sks cement followed w/5 sks Hulls in 100 sks cement w/500 Psi.

Remarks: By Allied.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 10-25-88

INV. NO. 22696

Signed Gilbert G. Scheck (TECHNICIAN)
D