

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-167-06740-00-03
Spot: SWSWSW Sec/Twnshp/Rge: 30-14S-13W
330 feet from S Section Line, 4950 feet from E Section Line
Lease Name: E. MILLER B Well #: 8
County: RUSSELL Total Vertical Depth: 2900 feet

Operator License No.: 34912
Op Name: C12 KANSAS OIL, LLC
Address: 1900 WAZEE ST. SUITE 200
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	6.625	2990	902	
SURF	15	39		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/24/2014 10:00 AM
Plug Co. License No.: 32128 Plug Co. Name: ROME CORPORATION DBA WESTERN WELL SERVICE
Proposal Rcvd. from: AVEN WEAVERLING Company: C-12 KANSAS OIL, LLC Phone: (785) 623-3595

Proposed Plugging Method: Ordered 100 sx class A cement and 425 sx 60/40 pozmix 4% gel cement.

Plugging Proposal Received By: RAY DINKEL Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/24/2014 4:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Perfs:

Perforated at 1450', 2030' and 2544'. Drilled down inside 6 5/8" casing to 2644' and perforated. Ran tubing to botom and pumped 100 sx Class A cement. Pulled tubing to 1471' and pumped 75 sx 60/40 pozmix 4% gel cement. Pulled tubing to 915' and pumped 100 sx 60/40 pozmix 4% gel cement. Pulled tubing to 350' and pumped 200 sx 60/40 pozmix 4% gel cement w/ 350 # hulls. Cement circulated. POOH. Pumped 20 sx cement and topped off 15" casing. Shut in.

GPS: 38.79931 -098.81667

Remarks: QUALITY CEMENTING TICKET # 674

Plugged through: TBG

District: 04

Signed Ray A. Dinkel
11/5/14 CKM (TECHNICIAN)

CM

OCT 27 2014

Form CP-2/3

Received
KANSAS CORPORATION COMMISSION
NOV 03 2014
CONSERVATION DIVISION
WICHITA, KS