

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-007-20283-00-00
Spot: SENENW Sec/Twnshp/Rge: 7-35S-14W
975 feet from N Section Line, 2198 feet from W Section Line
Lease Name: EWB RANCH Well #: A-1
County: BARBER Total Vertical Depth: 4940 feet

Operator License No.: 3532
Op Name: CMX, INC.
Address: 1700 N WATERFRONT PKWY BLDG 300
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4835		WITH 2 SX CMT
PROD	4.5	4930	3000	WITH 125 SX CMT
SURF	8.625	845		WITH 425 SX CMT

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 10/27/2014 10:00 AM
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION
Proposal Rcvd. from: MARK MORGENSTERN Company: CLARKE CORPORATION Phone: (620) 886-5665

Proposed Plugging Method: SET CIBP @ 4835' & 2 SX CMT. PLUG AT 900' WITH 10 SX GEL & 50 SX CMT. PLUG AT 300' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: LARRY HARRIS
Date/Time Plugging Completed: 10/27/2014 12:15 PM

Witness Type: COMPLETE (100%)
KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP @ 4835' & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. 1ST PLUG AT 919' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 317' WITH 50 SX CMT. 3RD PLUG AT 62' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4885	4895		

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

Received
KANSAS CORPORATION COMMISSION

NOV 03 2014

CONSERVATION DIVISION
WICHITA, KS

District: 01

Signed

Stephen J Pfeifer
(TECHNICIAN)
11/5/14 CEM

RECEIVED

OCT 30 2014

KCC DODGE CITY